

PROJECT METHOD STATEMENT				
GENERAL DET	AILS			
Project Name:	ClockedIn Ti	me & Attendance	Project Ref:	
Contractor / Subcontractor:		ClockedIn Ltd		
Prepared by:	Mark Shaw			
Method Statemer	nt Title:	Time & Attendance Installation		
Method Statement No.:		A001	Revision No.:	1
Task/Activity:		Time & Attendance Device Installation		
Site Foreman/Supervisor:		Mark Shaw		
Site Manager:		Mark Shaw		
H&S Representative: Mark Shaw				
HIGH RISK WO	ORKS			
High Risk Activity (Y/N):			No	
Recorded on High	n Risk Register	(Y/N):	No	
High Risk Workshop undertaken (Y/N + date):		n (Y/N + date):	No	

DOCUMENT REVIEW					
Reviewed by:	Name:	Signed:	Date:	Status:	
Mark Shaw	Mark Shaw	Mark Shaw	03.03.2023	1	

SECTION 1: DESCRIPTION OF WORKS (Brief Summary)

Installation of Time and Attendance Android and Kiosk

SECTION 2: KEY HAZARDS / RISKS (Refer to Risk Assessment/s)				
Hazards/Risks	Key Controls			
 Electrical Connection via 3-pin plug or connection to a pre-installed Non-Switched Fused Spur Drill 4 x 6mm holes in wall for mounting kiosk to 	Trained installer			
wall	Trained installer			

SECTION 3: SEQUENCE OF WORKS (Method)

- Arrive on-site and sign in as per site processes
- Ensure location of installation is safe and ready for installation
- Install angle bracket on wall by drilling 4 holes and affixing angle bracket to wall with 4 wall screws
- Attach kiosk to angle bracket with 4 screws
- Connect 5 volt charger to power source via 3-pin 240v plug or connect to pre-installed Non-Switched Fused Spur
- Place wire from power source to kiosk in pre-cut plastic conduit or trunking to secure wire
- Place Android tablet into kiosk and plug in charger cable to the tablet
- Place faceplate on to kiosk
- Provide appropriate user training

Review Status: 1 - Accepted 2 - Rejected, revision required



ECTION 4: SUPERVISION / LABOUR	
upervisor(s):	
1ark Shaw	
peratives:	
Mark Shaw	

SECTION 5: TEMPORARY WORKS (TW)

- No hot works required
- Total Installation time around 30 minutes


SECTION 7: PLANT & EQUIPMENT

• Plant and Equipment required:

Cordless Drill

• Electrical (include PAT):

Not required as the protection of appliances marked with this double square symbol is ensured by double insulation and does not require a safety connection to electrical earth or PAT testing



Tools:

Drill

Cross-head screwdriver - Medium

Electricians Flat-head screwdriver – Small

Small wire cutters

SECTION 8: MATERIALS

Junior Hacksaw

• Other:

N/A

Please comment "Yes / No" under the pictograms below Acute Toxicity Explosive Oxidising Flammable Corrosive Y / N: No Y / N: No Y / N: No Y / N: No Y / N: Gas Under Serious Health Health Hazard Hazardous to the Pressure Hazard Environment

Y / N: No

Y / N: No

• Materials required:

Y / N:


4 x Rawl Plugs

4 x Screws

Y / N: No



•	Storage:
	Not Required
•	Hazardous Substances/SDS:
	None
•	Waste Management:
	N/A



SECTION 10: PERMITS			
	Yes	No	Comments
Hotworks:		No	
Excavations:		No	
Roofworks:		No	
Temporary works		No	
Confined Spaces:		No	
Live Services:		No	
Risers/Shafts:		No	
Ladder:		No	
Works in ESB Hazard Zone:		No	
Other:		N/A	

SECTION 11: THIRD PARTY CO-ORDINATION

• None required



SECTION 12: RISK ASSESMENT ClockedIn Ltd LIKELIHOOD **Description of Work** Name of Task/Activity/Area **Risk Matrix** Installation of Time & Attendance Device Installation of Time and Attendance device **Work Start Date** TBC SEVERITY **Project Duration** 30 minutes Risk Rating Who might be harmed & how Hazards Identified Current Control Measures Improvement Actions Likelihood Severity Score 4 Trained Installer None Drill 4 holes in designated wall Installer – Drill bit could slip during operation Connect unit to power supply via 3-pin Installer - Electrocution 2 Trained Installer None plug or Non-Switch Fused Spur **Additional Notes:** Name: Mark Shaw **Further Assessments required?** None Position: ☐ Health Surveillance Installer COSHH Manual Handling ☐ Display Screen Equipment Other (please specify) Signature: N/A Mark Shaw **Date of Completion:** 3rd March 2023



SECTION 13: EMERGENCY PROCEDURES:				
TASK SPECIFIC EMERGENCY REQUIREMENTS:				
N/A				
ACCIDENT REPORTING:				
All accidents and incidents and near misses will be reported to Site management immediately to facilitate accident investigation and preservation of evidence.				
FIRST AIDER DETAILS:	Mark Shaw			
FIRST AID LOCATION:	On Site			
DETAILS OF NEAREST HOSPITAL:				
TBC				

SECTION 14: SUMMARY OF KEY ISSUES

The following is a summary of the key issues included in these RAMS. This is a non-exhaustive list that attempts to capture the main items to be implemented on site and to be monitored.

There are no key issues during the installation of these Time and Attendance Kiosk

This is a very low risk procedure

SECTION 15: CO	MMUNICATION OF	METHOD STATEN	1ENT		
Where those completing the works do not understand written English, the Method				Confirm	
Statement must be either:				(A / B)	
A) Translated in writing into native language and communicated				A	
B) Translated by interpreter to those completing the works					
Communication completed by: Name: Mark Shaw Signature: Mark Shaw					
I am familiar with the content of this Method Statement and will undertake the works in accordance					
with it. If the work activity changes from that outlined, I will stop works until a review can take place					
to ensure the safety of myself and others.					
NAME (PRINT)	SIGNATURE	NATIVE	UNDERSTAND	DATE	
		LANGUAGE	WRITTEN		
			ENGLISH (Y/N)		
Mark Shaw	Mark Shaw	English	Υ	03.03.2023	
Mark Silaw					
IVIAI K SIIAW					
IVIAI K SIIAW					